



COMMERCIAL TREE TIE SECURE TO STAKES. SET LOOSE TO ALLOW FOR TRUNK DIAMETER GROWTH. REMOVE STAKING AFTER 12 MONTHS

2"X2" DOUG FIR STAKES (2 PER TREE)

REMOVE TOP 1/2 OF BURLAP. PRUNE KINKED AND GIRDED ROOTS.

2" BARK MULCH - KEEP AWAY FROM TRUNK

BACKFILL PIT WITH NATIVE TOPSOIL PER WSDOT 8-0.3(4)B. REMOVE DEBRIS AND TRASH. GENTLY PACK AROUND BASE OF ROOTBALL TO STABILIZE WATER THOROUGHLY AND TAMP REST OF BACKFILL LIGHTLY.

ROOT BARRIER ALONG PAVEMENT 12-18" HEIGHT UP TO MAX 24" LENGTH

UNDISTURBED SUBGRADE

1/2 HEIGHT OF TREE

VARIES

1'-0"

ROOT COLLAR AND TOP OF ROOT BALL SHALL BE AT GRADE IN WELL-DRAINED SOIL; UP TO 4" ABOVE GRADE IN POORLY DRAINED SOILS. ROOT COLLAR MUST BE EXPOSED.

PLANTING PIT TO BE MIN 3X DIAMETER OF ROOT BALL  
BREAK DOWN SIDES OF PIT WHILE BACKFILLING

TREE PLANTING SHALL CONFORM TO THE REQUIREMENTS OF SECTION 8-.02 OF WSDOT/APWA STANDARDS.



# STANDARD TREE PLANTING

City of Snohomish Public Works Department

Approved By: \_\_\_\_\_

City Engineer

Date: \_\_\_\_\_

**800**  
Number